

Annual Visayas System Peak Demand per SubGrid as of 2015
in MW



Year	CEBU	% AAGR	NEGROS	% AAGR	PANAY	% AAGR	LEYTE-SAMAR	% AAGR	BOHOL	% AAGR	VISAYAS	% AAGR
1995	248		113		88		116		21		586	
1996	272	9.73	127	12.61	95	7.03	116	0.30	22	5.69	632	7.87
1997	291	7.10	141	10.66	114	20.76	152	30.41	24	7.17	722	14.15
1998	297	2.06	136	(3.70)	114	(0.47)	127	(15.96)	28	15.90	702	(2.79)
1999	333	12.16	152	12.03	81	(28.65)	126	(1.10)	30	8.66	722	2.97
2000	353	6.04	156	2.45	84	3.45	122	(3.25)	32	4.98	746	3.33
2001	377	6.65	151	(2.78)	146	73.92	156	28.09	31	(3.39)	861	15.33
2002	349	(7.40)	178	17.45	113	(22.39)	162	3.91	40	30.88	842	(2.16)
2003	422	20.97	179	0.94	105	(7.61)	175	7.93	41	3.28	923	9.54
2004	417	(1.14)	199	10.86	122	16.68	167	(4.52)	49	18.73	955	3.46
2005	438	4.94	195	(2.03)	120	(1.91)	168	0.65	46	(6.33)	967	1.28
2006	458	4.68	199	1.87	123	2.64	171	1.43	46	0.44	997	3.09
2007	477	4.12	209	5.11	182	48.20	186	8.76	49	5.42	1,102	10.61
2008	522	9.39	218	4.30	203	11.49	182	(2.21)	52	6.17	1,176	6.68
2009	559	7.07	215	(1.13)	223	9.91	188	3.49	56	7.77	1,241	5.52
2010	674	20.56	263	22.29	243	8.68	204	8.33	48	(14.21)	1,431	15.31
2011	704	4.44	245	(6.75)	260	7.25	209	2.81	62	30.83	1,481	3.50
2012	747	6.20	256	4.45	262	0.48	221	5.65	65	3.42	1,551	4.71
2013	780	4.41	253	(1.40)	272	3.82	199	(10.08)	63	(2.25)	1,567	1.01
2014	862	10.45	266	5.38	264	(2.72)	181	(8.74)	62	(2.23)	1,636	4.40
2015	850	(1.34)	309	15.92	309	16.84	230	26.54	70	14.18	1,768	8.09
AAGR												
1996-2015		6.39		5.05		8.44		4.32		6.81		5.69
2006-2015		7.26		5.35		11.55		3.84		5.46		6.65
2011-2015		4.93		6.09		4.61		3.34		3.28		4.55

Note:

1. November 22, 1998 Panay Electric Co. (PECO) was isolated from the system
2. Negros - Panay (100 MW) was interconnected thru Submarine Cable last October 17, 1990
3. Cebu - Negros was interconnected thru Submarine Cable last January 26, 1994 (Phase I) 100 MW and August 2008 (Phase II) 100 MW
4. Leyte-Cebu was interconnected last 1997 for Phase I (200 MW) and 2005 for Phase II (200 MW)
5. Leyte-Bohol was interconnected last 2000 for Phase I (50 MW) and 2002 for Phase II (50 MW)
6. Panay Power Corporation (PPC) availed ODPS Contract from July 1, 2001 to July 1, 2002
7. Panay demand increased due to PPC synchronized to the system on 6 June 2007
8. From 1998-2006 excludes demand of Panay Electric Co. (PPC) in Visayas Grid
9. New 610 MW Coal-fired power plant (246 MW CEDC, 200 MW KSPC, 164 MW PEDC)
10. Source of data from NGCP